



DISTRIBUTION WAREHOUSES, PETERBOROUGH

May 2022

www.aarsleff.co.uk

SCOPE OF WORKS 5090nr. precast concrete piles/72,278m of precast piles installed

EQUIPMENT x4 Junttan PM20/22 Rigs

CONTRACTOR Glencar Construction

CONSTRUCTION PERIOD January – May 2022



LARGE SCALE PILING FOR THREE NEW OFFICE/WAREHOUSE UNITS IN THE EAST OF ENGLAND

The 5090nr. 250mm type 4 piles were driven through made ground founding on mudstone at depths ranging between 13 to 16m; with small areas founding in stiff clays at 8m, installed utilising 4 No. PM20/22 piling rigs.

Arrival on site was met with a slower start than anticipated, with a lack of information meaning the delivery team were not able to progress as quickly as initially expected.

The Project Delivery Team maintained high standards of communication both with the client and between project management and site in order to progress forward.

Hard work put in throughout by the site team meant that despite delays, timelines created at the tender stage were met and even surpassed in some cases.

Jon Goodman, Contracts Engineer said:

“The site crews worked tirelessly to make up for lost hours surpassing tender targets when possible. The efforts of Paul Gulliver and the site team were great and very much appreciated.”

Aarsleff Ground Engineering Ltd is the UK trading arm of Danish contracting giant, Per Aarsleff A/S. Incorporated in the UK in 1991, Aarsleff Ground Engineering is one of the UK's leading ground engineering specialist contractors, with piling, geotechnical, and retaining walls divisions. An in-house design team means Aarsleff can offer you a full package of design and installation and we actively promote early consultation for value-engineering to give our clients the best service, design quality, safety factor, and value.

Designed. Delivered. Trusted.

Your ground engineering partner.

Aarsleff Ground Engineering
info@aarsleff.co.uk | Tel 01636 611140